

**OFFICE OF THE DEAN::ASSAM AGRICULTURAL UNIVERSITY  
RAHA::NAGAON::ASSAM::782103**

No: AAU/FY/Tech-62 (13) /2020-21

Dated:

**CORRIGENDUM FOR SHORT TENDER NOTICE**

In continuation to the earlier short tender notice vide NO. AAU/FY/Tech-62 (13)/ 2019-20/ 4810-15 dated 18.02.2020, it is informed that due to the lockdown on COVID- 19 during the month of March-May, the last date of submission of quotations is hereby extended for 15 days from the date of publication of this advertisement. The following points are notified as addendum to the earlier order:

1. The interested reputed manufacturer/ authorized dealer/ supplier should visit the site for physical verification of the layout and design of the modular fittings.
2. The outside water supply and electrifications should be quoted in the quotations as per actuals.
3. The requirement of different items and quantities are shown in **Annexure I**
4. The remaining terms and conditions and other specifications will remain the same as earlier order.


↑  
(K.K. Tamuli)  
Dean (i/c.)  
College of Fisheries  
AAU, Raha, Nagaon Assam

No: AAU/FY/Tech-62 (13)/2020-21/ 2470 - 74

Dated 19/06/2020

Copy forwarded for information and necessary action to:

1. The Coordinator, BIF & ARIS cell, CVSc, AAU, Khanapara, Guwahati-22 with a request to upload the detail advertisement in the College website.
2. The I/C, ARIS cell, AAU, Jorhat with a request to upload the detail advertisement in the University website.
3. Dr. B. Kalita, Co-Chairman, Project Implementation Committee, AAHL, CFSc, AAU, Raha
4. Mr. I.A. Hussain, Co-ordinator, Project Implementation Committee, AAHL, CFSc, AAU, Raha
5. Notice Board, The office of the Dean, CFSc, AAU, Raha
6. Office copy

  
Dean (i/c.)  
College of Fisheries  
AAU, Raha, Nagaon Assam

**ANNEXURE-I**

**Name of the Item: MODULAR FITTINGS FURNISHING & ACCESORIES OF LABORATORY**

<b>Sl. No.</b>	<b>Name of the item and specification</b>	<b>Quantity Required</b>	<b>Unit</b>
<b>WATER QUALITY LAB</b>			
<b>1.</b>	<b>ISLAND Bench (IB - 1) Size: L 3550 mm x W 1500 mm x H 900 mm</b>	<b>1.00</b>	<b>No.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	5.33	Sqm.
	750 mm wide storage module with one drawer two shutters	6.00	Nos.
	750 mm wide storage module with two shutters	1.00	Nos.
	500 mm wide storage module with one drawer one shutter	2.00	Nos.
	350 mm wide storage module with one drawer one shutter	2.00	Nos.
	Single piece molded PP sink (L 600 x W 450 x D 315)	1.00	Nos.
	Worktop mounted three way water tap with swan neck spout	1.00	Nos.
	Peg Board in Phenolic resin construction with 20 Nos. PP Pegs	1.00	Nos.
	Double sided double tier reagent rack with electrical raceway	2.80	Rmt.
	- 6/16 Amp electrical sockets and 16 Amp one way switch	19.00	Nos.
	MS Pipe for Granite Support	4.00	Nos.
	Filler Panel in G.I. Construction	2.00	Nos.
<b>STERILIZATION ROOM</b>			
<b>2.</b>	<b>Wall Bench (WB - 1) Size: L 3000 mm x W 900 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	2.70	Sqm.
	750 mm wide storage module with one drawer two shutters	3.00	Nos.
	750 mm wide storage module with two shutters	1.00	Nos.
	Single piece molded PP sink (L 600 x W 450 x D 315)	1.00	Nos.
	- Worktop mounted three way water tap with swan neck spout	1.00	Nos.
	Peg Board in Phenolic resin construction with 20 Nos. PP Pegs	1.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	2.25	Rmt.
		6.00	Nos.
	- 6/16 Amp electrical sockets and 16 Amp one way switch	1.00	Nos.
	MS Pipe for Granite Support	2.00	Nos.
	Filler Panel in G.I. Construction		

<b>MICROBIOLOGY LABORATORY</b>			
<b>3.</b>	<b>Wall Bench (WB - 2) Size: L 1939 mm x W 750 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	1.45	Sqm.
	750 mm wide storage module with one drawer two shutters	1.00	Nos.
	500 mm wide storage module with one drawer one shutter	2.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	1.94	Rmt.
		6.00	Nos.
	- 6/16 Amp electrical sockets and 16 Amp one way switch	1.00	Nos.
	Close Panel in G.I. Construction	2.00	Nos.
	Filler Panel in G.I. Construction		
<b>4.</b>	<b>Corner Bench (CB - 1) Size: L 1030 mm x W 1030 mm x H 900 mm</b>	<b>2.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	1.06	Sqm.
	Corner storage module with one shutter	1.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	2.06	Rmt.
		4.00	Nos.
	6/16 Amp electrical sockets and 16 Amp one way switch	2.00	Nos.
	Filler Panel in G.I. Construction		
<b>5.</b>	<b>ISLAND Bench (IB - 2) Size: L 1525 mm x W 1500 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	2.29	Sqm.
	750 mm wide storage module with one drawer two shutters	4.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	3.05	Rmt.
		8.00	Nos.
	6/16 Amp electrical sockets and 16 Amp one way switch	2.00	Nos.
	Filler Panel in G.I. Construction		
<b>6.</b>	<b>Wall Bench (WB - 3) Size: L 1939 mm x W 750 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	1.45	Sqm.
	750 mm wide storage module with two shutters	1.00	Nos.
	500 mm wide storage module with one drawer one shutter	2.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	1.00	Rmt.
	6/16 Amp electrical sockets and 16 Amp one way switch	4.00	Nos.
	Single piece molded PP sink (L 600 x W 450 x D 315)	1.00	Nos.
	Worktop mounted three way water tap with swan neck spout	1.00	Nos.

	Peg Board in Phenolic resin construction with 20 Nos. PP Pegs	1.00	Nos.
	Close Panel in G.I. Construction	1.00	Nos.
	Filler Panel in G.I. Construction	2.00	Nos.
<b>PCR INSTRUMENT</b>			
<b>7.</b>	<b>Wall Bench (WB - 4) Size: L 4658 mm x W 750 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	3.49	Sqm.
	750 mm wide storage module with one drawer two shutters	3.00	Nos.
	500 mm wide storage module with one drawer one shutter	1.00	Nos.
	- Leg space	3.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	4.66	Rmt.
		14.00	Nos.
	6/16 Amp electrical sockets and 16 Amp one way switch	1.00	Nos.
	- Close Panel in G.I. Construction	2.00	Nos.
	- Filler Panel in G.I. Construction		
<b>8.</b>	<b>Corner Bench (CB - 2) Size: L 1030 mm x W 1030 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	1.06	Sqm.
	Corner storage module with one shutter	1.00	Nos.
	Single piece molded PP sink (L 600 x W 450 x D 315)	1.00	Nos.
	Worktop mounted three way water tap with swan neck spout	1.00	Nos.
	Peg Board in Phenolic resin construction with 20 Nos. PP Pegs	1.00	Nos.
	- Filler Panel in G.I. Construction	2.00	Nos.
<b>9.</b>	<b>Wall Bench (WB - 5) Size: L 1933 mm x W 750 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	Work top in 18 ± 1 mm thick Black Granite construction	1.45	Sqm.
	750 mm wide storage module with one drawer two shutters	1.00	Nos.
	500 mm wide storage module with one drawer one shutter	1.00	Nos.
	Leg space	1.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	1.93	Rmt.
		6.00	Nos.
	6/16 Amp electrical sockets and 16 Amp one way switch	1.00	Nos.
	- Close Panel in G.I. Construction	2.00	Nos.
	Filler Panel in G.I. Construction		

<b>PCR SAMPLE INCULCATION ROOM</b>			
<b>100</b>	<b>Wall Bench (WB - 6) Size: L 2963 mm x W 900 mm x H 900 mm</b>	<b>1.00</b>	<b>Nos.</b>
	- Work top in 18 ± 1 mm thick Black Granite construction	2.67	Sqm.
	750 mm wide storage module with one drawer two shutters	2.00	Nos.
	750 mm wide storage module with two shutters	1.00	Nos.
	500 mm wide storage module with one drawer one shutter	1.00	Nos.
	Single piece molded PP sink (L 600 x W 450 x D 315)	1.00	Nos.
	Worktop mounted three way water tap with swan neck spout	1.00	Nos.
	Peg Board in Phenolic resin construction with 20 Nos. PP Pegs	1.00	Nos.
	Worktop mounted electrical raceway in GI powder coated construction	2.21	Rmt.
	6/16 Amp electrical sockets and 16 Amp one way switch	6.00	Nos.
	MS Pipe for Granite Support	1.00	Nos.
	- Close Panel in G.I. Construction	2.00	Nos.
	- Filler Panel in G.I. Construction		

Sd/-

**(K.K. Tamuli)**

Dean

CFSc, AAU, Raha, 782103